

Reel, Pole and Gas Trailers using ACME-Clamp™, Safelock™, and Securelock™ Technologies

SL SERIES with SAFELOCKTM TECHNOLOGY

OPERATOR'S MANUAL



BUILT FOR SAFETY. BUILT FOR SPEED. BUILT TO LAST.

WARNING

This User's Manual contains safety information and instructions for your trailer.

.YOU must read this manual before loading or towing your trailer.

YOU must follow all safety precautions and instructions.

SL SAFELOCK[™] SERIES REEL TRAILER SPECIFICATIONS

GENERAL SPECIFICATIONS:

CHASSIS:

• GVWR: 11,500 lbs @ 15% Tongue Wt.,

GVWR: 10,000 lbs. when De-Rated to avoid Class A CDL Requirement

• Unladen Weight: 2,000 lbs (approx.)

• Max Payload: 9,500 lbs (8,000 lbs. when De-rated)

• Axle: 10,000 lbs Dexter GD

• **Brakes:** Electric (12.25" x 3.375" forward self adjustment)

• Wheels: 17.5x6.75 HC/8 on 6.5 B.C. w/ .19 offset

• Tires: 215/75 R17.5 H

• Width: 96" (Fender to Fender)

• Length: 123"

• Hitch: 2.5" 4-Bolt Pintle, 20 Ton 6 Position Adjustable

• Fender: 1/8" Thk. Diamond Plate

Reel Specifications:

• Max Reel Weight: (1) @ 9,500 lbs , (8,000 lbs when De-rated)

Max Diameter: 96"

Max Width: 66"

Standard Features:

- SAFELOCK[™] Technology—Provides Industry Leading Safety, Ease of Use & Low Maintenance & Durability
- Jack (Front): 8K Side Wind
- Jacks (Stabilizers): (2) 8K Side Wind
- Safety Chains: (2) 3/8" Zinc Plated Grade 70 Alloy w/ Spring Clevis Hook
- DOT Reflective Tape (Conspicuity Tape) 50% length of Side & Rear
- Lighting: FMVSS / CMVSS Standard 108 LED Components



Safelock[™] Technology

SL SAFELOCK[™] SERIES REEL TRAILER SPECIFICATIONS

Standard Features (continued):

- LED Stop /Turn /Tail Lights Sealed and Grommet Mounted
- Clearance Lights: Rear Red / Front Amber
- Standard Finish: Paint
 - Paint Standard Colors: Red, Black, White, and CAT Yellow
 - All Seams Caulked
 - I.M.P.A.C.T. Intense Metal pH ACID Cleaning Technology Hydrofluoric, Sulfuric, Phosphoric ACID Bath
 - Rust Preventa □ve 2 □ Part Epoxy Primer
 - 2-Part Polyurethane Top Coats

Available Options:

- **3-Step Hot Dip Galvanizing** (Includes 10 Years Structural Warranty)
- 16" Bronze Ventilated Overspin Tension Brake
- 16" Hitch Extension
- Wheel Chocks (Rubber or All Weather Galvanized)
- Solar Charged Breakaway Kit
- Plug & Play Wiring System

AT REELSTRONG SAFETY IS #1 YOUR PINLESS TRAILER IS ENGINEERED WITH "SAFETY 1^{ST"} IN MIND

However, the operator must read all reel trailer safety information in this manual and on the trailer's warning, caution and informational stickers carefully and fully understand all applications and instructions in this manual before towing the trailer.

PRE-TRANSPORT INSTRUCTIONS

- MAKE SURE TRAILER IS PROPERLY CONNECTED TO TOW VEHICLE BEFORE LOADING OR UNLOAD-ING REELS. (SEE OPERATING INSTRUCTIONS FOR REEL LOADING/UNLOADING PROCEDURE)
- MAKE SURE THE TRAILER AND THE TOW VEHICLE WHEELS ARE PROPERLY CHOCKED AND STABILIZ-ING JACKS ARE LOWERED TO GRADE PRIOR TO LOADING, UNLOADING REEL OR DISTRIBUTING CA-BLE.
- MAKE SURE REEL IS CENTERED ON THE REEL BAR AND LOCK COLLARS SECURED BEFORE LOADING & TRANSPORT.
- MAKE SURE BOTH SAFELOCK LATCHES OF EACH REEL BAR POSITION ARE DEPRESSED AND IN THE LOCKED POSITION PRIOR TO LOADING OR TRANSPORT. SEE ILLUSTRATION ON FOLLOWING PAGE.
- MAKE SURE ALL NUTS, LUG NUTS, BOLTS, AND MECHANICAL DEVICES ARE TIGHT, SECURE, AND IN PROPER WORKING CONDITION.
- CONFIRM TIRES PROPERLY INFLATED (see manual for inflation instructions)
- VERIFY THE GVW WEIGHT RATING WILL NOT BE EXCEEDED PRIOR TO LOADING TRAILER.
- CONFIRM FRONT & REAR JACKS ARE RAISED TO THE HIGHEST POSITION PRIOR TO TOWING TRAILER.
- CONFIRM ALL HITCH MECHANISMS AND SAFETY CHAINS ARE PROPERLY ATTACHED AND SECURED.
- CONFIRM ALL ELECTRICAL CONNECTIONS & LIGHTS WORKING PROPERLY.
- CONFIRM BRAKES ARE WORKING PROPERLY BEFORE APPROACHING AN INCLINE, ENTERING TRAFFIC &/OR PUBLIC ROADS.

SAFETY ALERT SYMBOLS AND SIGNAL WORDS

An Owner's Manual that provides general trailer information cannot cover all specific details necessary for the proper combination of every trailer, tow vehicle and hitch. Therefore, you must read, understand and follow the instructions from the tow vehicle and trailer hitch manufacturers, as well as the instructions in this manual.


Our trailers are built with components produced by various manufacturers. Some of these items have separate instruction manuals. Where this manual indicates that you should read another manual, and you do not have that manual or know the manufacturer of that particular part, call Reelstrong at 484-889-8048 to find out how to get a free copy.

The safety information in this manual is denoted by the safety alert symbol: \land



Safety Placards & Decals

Shown below are some of the safety decals or placards used on the trailers. Failure to heed these warnings could result in road hazard, personal injury, or death. You must order replacements if any of these stickers are torn or have been removed or become illegible for any reason. Contact Reelstrong Utility Fleet at 484-889-8048.




Warning No.3

^WARNING

Loading/Unloading Procedures:

Loading:

Step 1: Ensure tow vehicle & trailer are on a level grade and trailer is connected securely to tow vehicle per hitch manufacturer's instructions. Connect safety chains crossing them per DOT regulations and securely attach breakaway switch to vehicle in such away as to ensure activation if trailer becomes unhitched for any reason. See illustration below as an example of good general practices for hitch connection.



Connect

trailer


Step

electrical connections and ensure all marker lights, brake lights and turn signals are functioning properly.

Step 3: Chock the wheels of the trailer and ensure the tow vehicle is prevented from moving with wheel chocks or other method that will provide safety and stability to the tow vehicle.

Step 4: If your trailer is equipped with front or rear stabilizing jacks lower them to grade.

Step 5: Pull the SafelockTM latches located on each end of the reel bars all the way out until the latch catches




and is held in the open position. (See illustration below)


Step 6: Using the lifting lug locations secure the reel bar properly with rigging suitable for the weight of the load

and lift the reel bar from the saddle. Center the reel across the reel bar using the centering collars. Secure the centering collars by tightening the set screws and jam nuts to help prevent loosening from vibration etc.

Step 7: Again ensure rigging is adequate to support the weight of the reel, wire/pipe and reel bar combined and lift and then lower the reel bar into the saddle taking care to align the reel bar drive and overspin tension brake coupler are properly aligned. (see illustration below)



Step 8: Close the SafelockTM latches located on each end of the reel bar. (See illustration below)



Step 9: Collect the Wheel Chocks and place them in a secure location.

(loading unloading procedure cont'd on following page)

Loading/Unloading Procedures: ^WARNING

Loading (continued)

Step 13: Raise the tongue jack & <u>ALL</u> the stabilizing jacks, walk around the vehicle one more time and confirm the brake away switch, chains, lights & brakes are connected and functioning properly.

Step 14: Before approaching a grade or entering traffic test your brakes for proper function.

Unloading Procedure:

Step 1: Make sure vehicle and trailer are on level ground and stabilized from movement with wheel chocks etc.

Step 2: Lower ALL stabilizing jacks to grade.

Step 3: Open SafelockTM Latches & remove Drive Pin(s) from Tension Brake & Power Winder if equipped with these options.

Step 4: Rig reel bar appropriately for estimated weight of reel, reel bar & payload.

Step 5: Lift and place reel on level ground using wheel chocks to stabilize against roll away.

Starting from the most dangerous at the top, the level of risk is indicated by the following signals:

^DANGER

DANGER-Immediate hazards which WILL result in severe personal injury or death if the warning is ignored.

^WARNING

WARNING-Hazards or unsafe practices which COULD result in severe personal injury or death if the warning is ignored.

^CAUTION

CAUTION-Hazards or unsafe practices which could result in minor or moderate injury if the warning is ignored.

^NOTICE

NOTICE—Practices that could result in damage to the trailer or other property.

MAINTENANCE OF MECHANICAL PARTS

Your reel trailer is only safe if properly maintained regularly. Always check to make sure all mechanical parts are in proper working condition before transporting reel trailer. Make sure all nuts and bolts are tight and weldments in satisfactory condition. Illustrated below are primary parts to maintain and make certain are in good working condition at all times.

HAZARDS

Loss of control of the trailer or trailer/tow vehicle combination can result in death or serious injury. The most common causes for loss of control of the trailer are:

- Improper sizing of the trailer for the tow vehicle, or vice versa.
- · Excessive Speed: Driving too fast for the conditions.
- · Failure to adjust driving behavior when towing a trailer.
- Overloading and/or improper weight distribution.
- Improper or mis-coupling of the trailer to the hitch.
- Improper braking and steering under sway conditions.
- Not maintaining proper tire pressure.
- · Not keeping lug nuts tight

IMPROPER SIZING OF THE TRAILER TO THE TOW VEHICLE

Trailers that weigh too much for the towing vehicle can cause stability problems, which can lead to death or serious injury. Furthermore, the additional strain put on the engine and drivetrain may lead to serious tow vehicle maintenance problems. For these reasons the maximum towing capacity of your towing vehicle should not be exceeded. The towing capacity of your tow vehicle, in terms of maximum Gross Trailer Weight (GTW) and maximum Gross Combined Weight Rating (GCWR) can be found in the tow vehicles Owner's Manual.

^DANGER

Use of tow vehicle with a towing capacity less than the Gross Vehicle Weight Rating of the trailer can result in loss of control, and may lead to death or serious injury.

Be sure your hitch and tow vehicle are rated for the Gross Vehicle Weight Rating of your trailer.

DRIVING TOO FAST

With ideal road conditions, the maximum recommended speed for safely towing a trailer is 60 mph. If you drive too fast, the trailer is more likely to sway, thus increasing the possibility for loss of control. Also your tires may overheat, thus increasing the possibility of a blowout.

^WARNING

Driving too fast for conditions can result in loss of control and cause death or serious injury. Decrease your speed when going downhill or as road, weather and lighting conditions deteriorate.

FAILURE TO ADJUST DRIVING BEHAVIOR WHEN TOWING A TRAILER

When towing a trailer, you will have decreased acceleration, increased stopping distance, and increased turning radius (which means you must make wider turns to keep from hitting curbs, vehicles, and anything else that is on the inside corner). Furthermore the trailer will change the handling characteristics of your towing vehicle, making it more sensitive to steering inputs and more likely to be pushed around in windy conditions or when being passed by large vehicles. In addition, you will need a longer distance to pass, due to slower acceleration and increased length. With these caveats in mind:

- Be alert for slippery conditions. You are more likely to be affected by slippery road surfaces when driving a tow vehicle with a trailer, than driving a tow vehicle without a trailer.
- Anticipate the trailer "swaying." Swaying can be caused by excessive steering, wind gusts, road-way edges, or by the trailer reaction to the pressure wave created by passing trucks and busses.
- When encountering trailer sway take your foot off the gas, and steer as little as possible in order to stay on the road. Use small "trim like" steering adjustments. Do not attempt to steer out of the sway; you'll only make it worse. Also do not apply the tow vehicle brakes to correct trailer swaying. On the other hand, application of the trailer brakes alone will tend to straighten out the combination, especially when going downhill.
- Check rearview mirrors frequently to observe the trailer & traffic.
- Use lower gear when driving down steep or long grades.
 Use the engine and transmission as a brake. Do not ride the brakes, as they can over heat and become ineffective.
- Be aware of your trailer height, especially when approaching bridges, roofed areas and around trees.

TRAILER NOT PROPERLY COUPLED TO THE HITCH

It is critical that the trailer be securely coupled to the hitch ball or pintle hitch, and that the safety chains and emergency break-away brake cable are correctly attached. Uncoupling may result in death or serious injury to you and to others.

^WARNING

Proper selection and condition of the coupler and hitch are essential to safely towing your trailer. A loss of coupling may result in death or serious injury.

- Be sure the maximum load rating of the hitch on the tow vehicle is equal to or greater than the maximum load rating of the coupler on the trailer.
 - Be sure the hitch ball or pintle hitch size matches the coupler size.
- Observe the hitch for wear, corrosion and cracks before coupling. Replace worn. corroded or cracked hitch components before coupling the trailer to the tow vehicle.
 - Be sure the hitch components are tight before coupling the trailer to the tow vehicle.

^WARNING

An improperly coupled trailer can result in death or serious injury.

DO NOT MOVE THE TRAILER UNTIL:

- The coupler is secured and locked to hitch ball;
- The safety chains are secured to the tow vehicle;
 - The trailer jack(s) are fully retracted.

DO NOT TOW THE TRAILER ON THE ROAD UNTIL:

- Tires and wheels are checked;
- The trailer brakes are checked;
- The breakaway switch is connected to the tow vehicle
- The load is secured to the trailer: and
- The trailer lights are connected and checked.

PROPER USE OF SAFETY CHAINS

If your trailer comes loose from the hitch for any reason, Reelstrong has provided safety chains so that control of the trailer can still be maintained.

^WARNING

Improper rigging of the safety chains can result in loss of control of the trailer and tow vehicle, leading to death or serious injury, if the trailer uncouples from the tow vehicle.

- Fasten chains to frame of tow vehicle. Do not fasten chains to any part of the hitch unless the hitch has holes or loops specifically for that purpose.
- Cross chains underneath hitch and coupler with enough slack to permit turning and to hold tongue up, if the trailer comes loose.

PROPER CONNECTION OF BREAKAWAY BRAKE

If equipped with brakes your trailer will be equipped with a breakaway brake system that can apply the brakes on your trailer if your trailer comes loose from the hitch ball for any reason. You will have a separate set of instructions for the breakaway brake if your trailer is so equipped. The breakaway brake system, including battery, must be in good condition and properly rigged to be effective.

^WARNING

An ineffective or inoperative breakaway brake system can result in a runaway trailer, leading to death or serious injury, if the coupler or hitch fails. The breakaway cable must be connected to the tow vehicle; and NOT to any part of the hitch. Before towing the trailer, test the function of the breakaway brake system. If the breakaway brake system is not working, do not tow the trailer; have it serviced or repaired.

MATCHING TRAILER AND HITCH

^DANGER

Use of a hitch with a load rating less than the load rating of the trailer can result in loss of control and may lead to death or serious injury.

WORN TIRES, LOOSE WHEELS AND LUG NUTS

Just as with your tow vehicle the trailer tires and wheels are important safety items. Therefore, it is essential to inspect the trailer tires before each tow.

If a tire has a bald spot, bulge, cut, cracks, or is showing any cords, replace the tire before towing. If a tire has uneven tread wear, take the trailer to a dealer service center for diagnosis. Uneven tread wear can be caused by tire imbalance, axle misalignment or incorrect inflation.

Tires with too little tread will not provide adequate frictional forces on wet roadways and can result in loss of control, leading to death or serious injury.

Improper tire pressure causes increased tire wear and may reduce trailer stability, which can result in a tire blowout or possible loss of control. Therefore, before each tow you must also check the tire pressure. Remember, the proper tire pressure is listed on the Certification / VIN label, normally mounted on the front Driver's side of the trailer, and should be checked when tires are cold. Allow 3 hours cool-down after driving as much as 1 mile at 40 mph before checking tire pressure.

^WARNING

Improper tire pressure can result in a blowout and loss of control, which can lead to death or serious injury.

Be sure tires are inflated to pressure indicated on the Certification / VIN label before towing trailer.

LUG NUT TIGHTNESS

The tightness of the lug nuts is very important in keeping the wheels properly seated to the hub!

Before each tow, check to make sure they are tight.

^WARNING

Metal creep between the wheel rim and hub may cause lug nuts to loosen and could result in a wheel coming off, leading to death or serious injury.

Tighten lug nuts before each tow.

The proper tightness (torque) for lug nuts is listed in Section 3.1.1 Use a torque wrench to tighten the lug nuts, use the crisscross star pattern. If you do not have a torque wrench, use a lug wrench (from your tow vehicle) and tighten the nuts as

much as you can. At the first opportunity, have a service garage or trailer dealer tighten the lug nuts to the proper torque.

Lug nuts are also prone to loosen after first being assembled. When driving a new trailer (or after wheels have been remounted), check to make sure they are tight after the first 10, 25 and 50 miles of driving and before each tow thereafter.

Failure to perform this check can result in a wheel separating from the trailer and a crash, leading to death or serious injury.

^WARNING

Lug nuts are prone to loosen after initial installation, which can lead to death or serious injury. Check lug nuts for tightness on a new trailer or when wheel(s) have been remounted after the first 10, 25 and 50 miles of driving.

^WARNING

Improper lug nut torque can cause a wheel separating from the trailer, leading to death or serious injury. Be sure lug nuts are tight before each tow.

IMPROPER LOADING

The total weight of the load you put in or on the trailer, plus the empty weight of the trailer itself, must not exceed the trailer's Gross Vehicle Weight Rating. If you do not know the empty weight of the trailer plus the cargo weight, you must weigh the loaded trailer at a commercial scale. Your trailer is equipped with a Tire & Loading Information Placard, mounted next to the Certification / VIN label, the cargo capacity weight stated on that placard is only a close estimate. The GVWR and GAWR's are listed on the Certification / VIN label mounted on the front left side of the trailer.

^WARNING

An overloaded trailer can result in loss of control of the trailer, leading to death or serious injury. Do not exceed the trailer Gross Vehicle Weight Rating (GVWR) or an axle Gross Axle Weight Rating (GAWR). Do not load a trailer so that the weight on any tire exceeds its rating.

UNSAFE LOAD DISTRIBUTION

Improper load distribution can lead to poor trailer sway stability or poor tow vehicle handling. Poor trailer sway stability results from tongue weights that are too low, and poor tow vehicle stability results from tongue weights that are too high. Refer to Chapter heading "Loading the Trailer" for more information.

In the table below, the second column shows the rule of thumb percentage of total weight of the trailer plus its cargo (Gross Trailer Weight, or "GTW") that should appear on the tongue of the trailer.

After loading, be sure to check that none of the axles are overloaded.

	as a Percentage of ailer Weight
Type of Hitch	Percentage
Pintle Hitch	10-15%

^WARNING

Improper tongue weight (load distribution) can result in loss of control of the trailer, leading to death or serious injury. Make certain that tongue weight is within the allowable range.

Be sure to: Center distribute the load properly.

SHIFTING REEL

You must center the reel from side-to-side so that it does not shift while the trailer is being towed. Your reel trailer is only safe as long as all local and state speed limits are obeyed and the reel is centered with the centering collars locked in place. Uneven left / right load distribution can cause tire, wheel, axle or structural malfunction and void your manufacturer's warranty.

^WARNING

Shifting reel can result in loss of control of the trailer, and can lead to death or serious injury. Make sure to tighten spool collars so that reel is centered on trailer before transport.

INAPPROPRIATE CARGO

Your trailer is only designed to transport cable reels and accessories. A cable reel trailer must not be used to carry items such as people, containers of hazardous substances and containers of flammable substances.

^WARNING

Do not transport people or any other items that are not intended to be transported by the trailer. The transport of people puts their lives at risk and may be illegal.

^WARNING

Do not transport flammable, explosive, poisonous or other dangerous materials in or on your trailer.

Exceptions:

 Battery stored on trailer used to power electric hydraulic unit.

INOPERABLE BRAKES, LIGHTS OR MIRRORS

Be sure that the electric brakes and all of the lights on your trailer are functioning properly before towing your trailer. Electric brakes and lights on a trailer are controlled via a connection to the tow vehicle, generally a multi-pin electrical connector. Check the trailer tail lights by turning on your tow vehicle headlights. Check the trailer brake lights by having someone step on the tow vehicle brake pedal while you look at trailer lights. Do the same thing to check the turn signal lights.

Your tow vehicle must have an electric brake controller that sends power to the trailer brakes. Before towing the trailer on the road, you must operate the brake controller while trying to pull the trailer in order to confirm that the electric brakes operate. While towing the trailer at less than 5 mph, manually operate the electric brake controller in the tow vehicle cab. You should feel the operation of the trailer brakes.

^WARNING

Improper electrical connection between the tow vehicle and the trailer will result in inoperable lights and electric brakes, and can lead to collision.

Before each tow:

- Check that the taillights, brake lights and turn signals work.
- Check that the electric brakes work by operating the brake controller inside the tow vehicle.

Standard mirrors usually do not provide adequate visibility for viewing traffic to the sides and rear a towed trailer. You must provide mirrors that allow you to safely observe approaching traffic.

^WARNING

To protect you and others against death or serious injury, all of the labels shown above must be on the trailer and be legible.

If any of these labels are missing or cannot be read, call Reelstrong at 484.889.8048 for free replacement labels.

HAZARDS FROM MODIFYING YOUR TRAILER

Essential safety items can be damaged by altering your trailer. Even simply adding a small weldment can damage an electrical circuit, or other feature of the trailer.

Before making any alteration to your trailer, contact your dealer or Reelstrong and describe the alteration you are contemplating. Alteration of the trailer structure or modification of mechanical, electrical, or other systems on your trailer must be performed only by qualified technicians who are familiar with the systems installed on your trailer. Any alteration to your Reelstrong trailer without written approval from Reelstrong INTL will void the warranty.

SAFETY WARNING LABELS ON YOUR TRAILER

The following is an assemblage of our trailer warning and caution stickers that must be present on the trailer in order for the trailer operator to understand the safe operation of the reel trailer. If any of these stickers is unreadable, missing or damaged call your local Reelstrong dealer or Reelstrong at 484-889-8048 for a free replacement label.

GENERAL TRAILER TOWING GUIDE

Driving a vehicle with a trailer in tow is vastly different from driving the same vehicle without a trailer in tow. Acceleration, maneuverability and braking are all diminished with a trailer in tow. It takes longer to get up to speed; you need more room to turn and pass, and more distance to stop when towing a trailer. You will need to spend time adjusting to the different feel and maneuverability of the tow vehicle with a loaded trailer. Because of the significant differences in all aspects of maneuverability when towing a trailer, the hazards and risks of injury are also much greater than when driving without a trailer. You are responsible for keeping your vehicle and trailer in control, and for all the damage that is caused if you lose control of your vehicle and trailer.

As you did when learning to drive an automobile, find an open area with little or no traffic for your first practice trailering. Of course, before you start towing the trailer, you must follow all of the instructions for inspection, testing, loading and coupling. Also, before you start towing, adjust the mirrors so you can see the trailer as well as the area to the rear of it. Drive slowly at first, 5 mph or so, and turn the wheel to get the feel of how the tow vehicle and trailer combination responds. Next, make some right and left hand turns. Watch in your side mirrors to see how the trailer follows the tow vehicle. Turning with a trailer attached requires more room.

Stop the rig a few times from speeds no greater than 10 mph. If your trailer is equipped with brakes, try using different combinations of trailer/electric brake and tow vehicle brake. Note the effect that the trailer brakes have when they are the only brakes used. When properly adjusted, the trailer brakes will come on just before the tow vehicle brakes.

It will take practice to learn how to back up a tow vehicle with a reel trailer attached. Short length trailers with single axles are difficult to back up without jack-knifing. Take it slow. Before backing up, get out of the tow vehicle and look behind the trailer to make sure that there are no obstacles. Some drivers place their hands at the bottom of the steering wheel, and while the tow vehicle is in reverse, "think" of the hands as being on the top of the wheel. When the hands move to the right (counter-clockwise, as you would do to turn the tow vehicle to the left when moving forward), the rear of the trailer moves to the right. Conversely, rotating the steering wheel clockwise with your hands at the bottom of the wheel will move the rear of the trailer to the left, while backing up. If you are towing a bumper hitch rig, be careful not to allow the trailer to turn too much, because it will hit the rear of the tow vehicle. To straighten the rig, either pull forward, or turn the steering wheel in the opposite direction.

REPORTING SAFETY DEFECTS

If you believe that your vehicle has a defect that could cause a crash or could cause injury or death, you should immediately inform the National Highway Traffic Safety Administration (NHTSA) in addition to notifying Reelstrong.

If NHTSA receives similar complaints, it may open an investigation, and if it finds that a safety defect exists in a group of vehicles, it may order a recall and remedy campaign. However, NHTSA cannot become involved in individual problems between you, your dealer and Reelstrong.

To contact NHTSA, you may either call the Vehicle Safety Hotline toll-free at 1-888-327-4236 (TTY: 1-800-424-9153), go tohttp://www.safecar.gov; or write to: Administrator, NHTSA, 400 Seventh Street, SW., Washington, DC 20590. You can also obtain other information about motor vehicle safety from http://www.safecar.gov.

Call Reelstrong at 484-889-8048 should you have any concerns regarding the latter information.

ADDITIONAL SAFE TRAILER TOWING GUIDELINES

- Before towing, check coupling, safety chain, safety brake, tires, wheels and lights.
- · Check the lug nuts or bolts for tightness.
- Check coupler tightness after towing 50 miles.
- Adjust the brake controller to engage the trailer brakes before the tow vehicle brakes. Follow the instructions given with the brake controller manufacturer's literature.
- Use your mirrors to verify that you have room to change lanes or pull into traffic.
- · Use your turn signals well in advance.
- Allow plenty of stopping space for your trailer and tow vehicle.
- Do not drive so fast that the trailer begins to sway due to speed. Generally never drive faster than 60 m.p.h.
- Allow plenty of room for passing. A rule of thumb is that the passing distance with a trailer is 4 times the passing distance without a trailer.
- Shift your automatic transmission into a lower gear for city driving.
- Use lower gears for climbing and descending grades.
- Do not ride the brakes while descending grades, they may get so hot that they stop working. Then you will potentially have a runaway tow vehicle and trailer.
- To conserve fuel, don't use full throttle to climb a hill. Instead, build speed on the approach.
- Slow down for bumps in the road. Take your foot off the brake when crossing the bump.

- Do not brake while in a curve unless absolutely necessary. Instead, slow down before you enter the curve.
- Do not apply the tow vehicle brakes to correct extreme trailer swaying. Instead, lightly apply the trailer brakes with the hand controller.
- · Make regular stops, about once each hour.

Confirm that:

- -The coupler is secure to the hitch and is locked,
- -Electrical connectors are made,
- -There is appropriate slack in the safety chains,
- There is appropriate slack in the breakaway switch pull-pin cable,
- -The tires are not visibly low on pressure, and
- -The cargo is secure and in good condition.

TIRE SAFETY INFORMATION

This portion of the User's Manual contains tire safety information as required by 49 CFR 575.6.

Section 2.1 contains "Steps for Determining Correct Load Limit - Trailer".

Section 2.2 contains "Steps for Determining Correct Load Limit - Tow Vehicle".

Section 2.3 contains a Glossary of Tire Terminology, including "cold inflation pressure", "maximum inflation pressure", "recommended inflation pressure", and other non-technical terms.

Section 2.4 contains information from the NHTSA brochure entitled "Tire Safety – Everything Rides On It".

This brochure describes the following items;

- Tire labeling, including a description and explanation of each marking on the tires, and information about the DOT Tire Identification Number (TIN).
- Recommended tire inflation pressure, including a description and explanation of:
- A. Cold inflation pressure.
- B. Vehicle Placard and location on the vehicle.
- C. Adverse safety consequences of under inflation (including tire failure).
- D. Measuring and adjusting air pressure for proper inflation.
- Tire Care, including maintenance and safety practices.
- Vehicle load limits, including a description and explanation of the following items:


A. Locating and understanding the load limit information, total load capacity, and cargo capacity.

B. Calculating total and cargo capacities with varying seating configurations including quantitative examples showing / illustrating how the vehicles cargo and luggage capacity decreas-

es as combined number and size of occupants' increases. This item is also discussed in Section 3.

- C. Determining compatibility of tire and vehicle load capabilities.
- D. Adverse safety consequences of overloading on handling and stopping on tires.

Actual tire size and weight limits are different than shown below.



STEPS FOR DETERMINING CORRECT LOAD LIMIT—TRAILER

TRAILERS 10,000 POUNDS GVWR OR LESS

- 1. Locate the statement, "The weight of cargo should never exceed XXX kg or XXX lbs.," on your vehicle's placard. See figure 1-1.
- 2. This figure equals the available amount of reel weight capacity which is 5,000 lbs.
- Determine the combined weight of reel being loaded on the vehicle. That weight may not safely exceed the available cargo capacity.

The trailer's placard refers to the Tire Information Placard attached adjacent to or near the trailer's VIN (Certification) label at the left front of the trailer.

GLOSSARY OF TIRE TERMINOLOGY

Accessory Weight

The combined weight (in excess of those standard items which may be replaced) of automatic transmission, power steering, power brakes, power windows, power seats, radio and heater, to the extent that these items are available as factory-installed equipment (whether installed or not).

Bead

The part of the tire that is made of steel wires, wrapped or reinforced by ply cords and that is shaped to fit the rim.

Bead Separation

This is the breakdown of the bond between components in the bead.

Bias Ply Tire

A pneumatic tire in which the ply cords that extend to the beads are laid at alternate angles substantially less than 90 degrees to the centerline of the tread.

Carcass

The tire structure, except tread and sidewall rubber which, when inflated, bears the load.

Chunking

The breaking away of pieces of the tread or sidewall.

Cold Inflation Pressure

The pressure in the tire before you drive

Cord

The strands forming the plies in the tire.

Cord Separation

The parting of cords from adjacent rubber compounds.

Cracking

Any parting within the tread, sidewall, or inner liner of the tire extending to cord material.

CT

A pneumatic tire with an inverted flange tire and rim system in which the rim is designed with rim flanges pointed radially inward and the tire is designed to fit on the underside of the rim in a manner that encloses the rim flanges inside the air cavity of the tire.

Curb Weight

The weight of a motor vehicle with standard equipment including the maximum capacity of fuel, oil, and coolant, and, if so equipped, air conditioning and additional weight optional engine.

Extra Load Tire

A tire designed to operate at higher loads and at higher inflation pressures than the corresponding standard tire.

Groove

The space between two adjacent tread ribs.

Innerliner

The layer(s) forming the inside surface of a tubeless tire that contains the inflating medium within the tire.

Innerliner Separation

The parting of the innerliner from cord material in the carcass.

Intended outboard sidewall

The sidewall that contains a white-wall, bears white lettering or bears manufacturer, brand, and/or model name molding that is higher or deeper than the same molding on the other sidewall of the tire or the outward facing sidewall of an asymmetrical tire that has a particular side that must always face outward when mounted on a vehicle.

Light Truck (LT) Tire

A tire designated by its manufacturer as primarily intended for use on lightweight trucks or multipurpose passenger vehicles.

Load Rating

The maximum load that a tire is rated to carry for a given inflation pressure.

Maximum Load Rating

The load rating for a tire at the maximum permissible inflation pressure for that tire.

Maximum Permissible Inflation Pressure

The maximum cold inflation pressure to which a tire may be inflated.

Maximum Loaded Vehicle Weight

The sum of curb weight, accessory weight, vehicle capacity weight, and production options weight.

Measuring Rim

The rim on which a tire is fitted for physical dimension requirements.

Non-pneumatic Rim

A mechanical device which, when a non-pneumatic tire assembly incorporates a wheel, supports the tire, and attaches, either integrally or separably, to the wheel center member and upon which the tire is attached.

Non-pneumatic Spare Tire Assembly

A non-pneumatic tire assembly intended for temporary use in place of one of the pneumatic tires and rims that are fitted to a passenger car in compliance with the requirements of this standard.

Non-pneumatic Tire

A mechanical device which transmits, either directly or through a wheel or wheel center member, the vertical load and tractive forces from the roadway to the vehicle, generates the tractive forces that provide the directional control of the vehicle and does not rely on the containment of any gas or fluid for providing those functions.

Non-pneumatic Tire Assembly

A non-pneumatic tire, alone or in combination with a wheel or wheel center member, which can be mounted on a vehicle.

Normal Occupant Weight

This means 68 kilograms (150 lbs.) times the number of occupants specified in the second column of Table I of 49 CFR 571.110.

Occupant Distribution

The distribution of occupants in a vehicle as specified in the third column of Table I of 49 CFR 571.110.

Open Splice

Any parting at any junction of tread, sidewall, or innerliner that extends to cord material.

Outer Diameter

The overall diameter of an inflated new tire.

Overall Width

The linear distance between the exteriors of the sidewalls of an inflated tire, including elevations due to labeling, decorations, or protective bands or ribs.

Ply

A layer of rubber-coated parallel cords.

Ply Separation

A parting of rubber compound between adjacent plies.

Pneumatic Tire

A mechanical device made of rubber, chemicals, fabric and steel or other materials, that, when mounted on an automotive wheel, provides the traction and contains the gas or fluid that sustains the load.

Production Options Weight

The combined weight of those installed regular production options weighing over 2.3 kilograms (5 lbs.) in excess of those standard items which they replace, not previously considered in curb weight or accessory weight, including heavy duty brakes, ride levelers, roof rack, heavy duty battery, and special trim.

Radial Ply Tire

A pneumatic tire in which the ply cords that extend to the beads are laid at substantially 90 degrees to the centerline of the tread.

Recommended Inflation Pressure

This is the inflation pressure provided by the vehicle manufacturer on the Tire Information label and on the Certification / VIN tag.

Reinforced Tire

A tire designed to operate at higher loads and at higher inflation pressures than the corresponding standard tire.

Rim

A metal support for a tire or a tire and tube assembly upon which the tire beads are seated.

Rim Diameter

This means the nominal diameter of the bead seat.

Rim Size Designation

This means the rim diameter and width.

Rim Type Designation

This means the industry of manufacturer's designation for a rim by style or code.

Rim Width

This means the nominal distance between rim flanges.

Section Width

The linear distance between the exteriors of the sidewalls of an inflated tire, excluding elevations due to labeling, decoration, or protective bands.

Sidewall

That portion of a tire between the tread and bead.

Sidewall Separation

The parting of the rubber compound from the cord material in the sidewall.

Special Trailer (ST) Tire

The "ST" is an indication the tire is for trailer use only.

Test Rim

The rim on which a tire is fitted for testing, and may be any rim listed as appropriate for use with that tire.

Tread

That portion of a tire that comes into contact with the road.

Tread Rib

A tread section running circumstantially around a tire.

Tread Separation

Pulling away of the tread from the tire carcass.

Treadwear Indicators (TWI)

The projections within the principal grooves designed to give a visual indication of the degrees of wear of the tread.

Vehicle Capacity Weight

The rated cargo and luggage load plus 68 kilograms (150 lbs.) times the vehicle's designated seating capacity.

Vehicle Maximum Load on the Tire

The load on an individual tire that is determined by distributing to each axle its share of the maximum loaded vehicle weight and dividing by two.

Vehicle Normal Load on the Tire

The load on an individual tire that is determined by distributing to each axle its share of the curb weight, accessory weight, and normal occupant weight (distributed in accordance with Table I of CRF 49 571.110) and dividing by 2.

Weather Side

The surface area of the rim not covered by the inflated tire.

Wheel Center Member

In the case of a non-pneumatic tire assembly incorporating a wheel, a mechanical device which attaches, either integrally or separably, to the non-pneumatic rim and provides the connection between the non-pneumatic rim and the vehicle; or, in the case of a non-pneumatic tire assembly not incorporating a wheel, a mechanical device which attaches, either integrally or separably, to the non-pneumatic tire and provides the connection between tire and the vehicle.

Wheel-holding Fixture

The fixture used to hold the wheel and tire assembly securely during testing.

TIRE SAFETY-REELSTRONG RIDES ON IT

The National Traffic Safety Administration (NHTSA) has published a brochure (DOT HS 809 361) that discusses all aspects of Tire Safety, as required by CFR 575.6. This brochure is reproduced in part below. It can be obtained and downloaded from NHTSA, free of charge, from the following web site:

http://www.nhtsa.dot.gov/cars/rules/TireSafety ridesonit/tires_index.html

Studies of tire safety show that maintaining proper tire pressure, observing tire and vehicle load limits (not carrying more weight in your vehicle than your tires or vehicle can safely handle), avoiding road hazards, and inspecting tires for cuts, slashes, and other irregularities are the most important things you can do to avoid tire failure, such as tread separation or blowout and flat tires. These actions, along with other care and maintenance activities, can also:

- · Improve vehicle handling
- Help protect you and others from avoidable breakdowns and accidents
- · Improve fuel economy
- · Increase the life of your tires.

This booklet presents a comprehensive overview of tire safety, including information on the following topics:

- · Basic tire maintenance
- · Uniform Tire Quality Grading System
- · Fundamental characteristics of tires
- · Tire safety tips.

Use this information to make tire safety a regular part of your vehicle maintenance routine. Recognize that the time you spend is minimal compared with the inconvenience and safety consequences of a flat tire or other tire failure.

SAFETY FIRST-BASIC TIRE MAINTENANCE

Properly maintained tires improve the steering, stopping, traction, and load-carrying capability of your vehicle. Underinflated tires and overloaded vehicles are a major cause of tire failure. Therefore, as mentioned above, to avoid flat tires and other types of tire failure, you should maintain proper tire pressure, observe tire and vehicle load limits, avoid road hazards, and regularly inspect your tires.

FINDING YOUR VEHICLE'S RECOMMENDED TIRE PRESSURE AND LOAD LIMITS

Tire information placards and vehicle certification labels contain information on tires and load limits. These labels indicate the vehicle manufacturer's information including:

- · Recommended tire size
- Recommended tire inflation pressure
- Vehicle capacity weight (VCW-the maximum occupant and cargo weight a vehicle is designed to carry)
- Front and rear gross axle weight ratings (GAWR- the maximum weight the axle systems are designed to carry).

Both placards and certification labels are permanently attached to the trailer near the left front.

other object or if you strike the curb when parking.

• With radial tires, it is usually not possible to determine under-inflation by visual inspection.

For convenience, purchase a tire pressure gauge to keep in your vehicle. Gauges can be purchased at tire dealerships, auto supply stores, and other retail outlets. The recommended tire inflation pressure that vehicle manufacturers provide reflects the proper psi when a tire is cold. The term cold does not relate to the outside temperature. Rather, a cold tire is one that has not been driven on for at least three hours. When you drive, your tires get warmer, causing the air pressure within them to increase. Therefore, to get an accurate tire pressure reading, you must measure tire pressure when the tires are cold or compensate for the extra pressure in warm tires.

UNDERSTANDING TIRE PRESSURE AND LOAD LIMITS

Tire inflation pressure is the level of air in the tire that provides it with load-carrying capacity and affects the overall performance of the vehicle. The tire inflation pressure is a number that indicates the amount of air pressure – measured in pounds per square inch (psi) – a tire requires to be properly inflated. (You will also find this number on the vehicle information placard expressed in kilopascals (kPa), which is the metric measure used internationally.)

Manufacturers of passenger vehicles and light trucks determine this number based on the vehicle's design load limit, that is, the greatest amount of weight a vehicle can safely carry and the vehicle's tire size. The proper tire pressure for your vehicle is referred to as the "recommended cold inflation pressure." (As you will read below, it is difficult to obtain the recommended tire pressure if your tires are not cold.)

Because tires are designed to be used on more than one type of vehicle, tire manufacturers list the "maximum permissible inflation pressure" on the tire sidewall. This number is the greatest amount of air pressure that should ever be put in the tire under normal driving conditions.

CHECKING TIRE PRESSURE

It is important to check your vehicle's tire pressure at least once a month for the following reasons:

- · Most tires may naturally lose air over time.
- · Tires can lose air suddenly if you drive over a pothole or

STEPS FOR MAINTAINING PROPER TIRE PRESSURE

- Step 1: Locate the recommended tire pressure on the vehicle's tire information placard, certification label, or in the owner's manual.
- · Step 2: Record the tire pressure of all tires.
- Step 3: If the tire pressure is too high in any of the tires, slowly release air by gently pressing on the tire valve stem with the edge of your tire gauge until you get to the correct pressure.
- Step 4: If the tire pressure is too low, note the difference between the measured tire pressure and the correct tire pressure. These "missing" pounds of pressure are what you will need to add
- Step 5: At a service station, add the missing pounds of air pressure to each tire that is under inflated.
- Step 6: Check all the tires to make sure they have the same air pressure (except in cases in which the front and rear tires are supposed to have different amounts of pressure).

If you have been driving your vehicle and think that a tire is under-inflated, fill it to the recommended cold inflation pressure indicated on your vehicle's tire information placard or certification label. While your tire may still be slightly under-inflated due to the extra pounds of pressure in the warm tire, it is safer to drive with air pressure that is slightly lower than the vehicle manufacturer's recommended cold inflation pressure than to drive with a significantly under-inflated tire. Since this is a temporary fix, don't forget to recheck and adjust the tire's pressure when you can obtain a cold reading.

TIRE SIZE

To maintain tire safety, purchase new tires that are the same size as the vehicle's original tires or another size recommended by the manufacturer. Look at the tire information placard, the owner's manual, or the sidewall of the tire you are replacing to find this information. If you have any doubt about the correct size to choose, consult with Reelstrong.

TIRE TREAD

The tire tread provides the gripping action and traction that prevent your vehicle from slipping or sliding, especially when the road is wet or icy. In general, tires are not safe and should be replaced when the tread is worn down to 1/16 of an inch. Tires have built-in tread-wear indicators that let you know when it is time to replace your tires. These indicators are raised sections spaced intermittently in the bottom of the tread grooves. When they appear "even" with the outside of the tread, it is time to replace your tires. Another method for checking tread depth is to place a penny in the tread with Lincoln's head upside down and facing you. If you can see the top of Lincoln's head, you are ready for new tires.

TIRE BALANCE AND WHEEL ALIGNMENT

To avoid vibration or shaking of the vehicle when a tire rotates, the tire must be properly balanced. This balance is achieved by positioning weights on the wheel to counterbalance heavy spots on the wheel-and-tire assembly. A wheel alignment adjusts the angles of the wheels so that they are positioned correctly relative to the vehicle's frame. This adjustment maximizes the life of your tires. These adjustments require special equipment and should be performed by a qualified technician.


TIRE REPAIR

The proper repair of a punctured tire requires a plug for the hole and a patch for the area inside the tire that surrounds the puncture hole. Punctures through the tread can be repaired if they are not too large, but punctures to the sidewall should not be repaired. Tires must be removed from the rim to be properly inspected before being plugged and patched.

TIRE FUNDAMENTALS

Federal law requires tire manufacturers to place standardized information on the sidewall of all tires. This information identifies and describes the fundamental characteristics of the tire and also provides a tire identification number for safety standard certification and in case of a recall. Information on Passenger Vehicle Tires

Please refer to the diagram below.



P

The "P" indicates the tire is for passenger vehicles.

Next Number

This three-digit number gives the width in millimeters of the tire from sidewall edge. In general, the larger the number, the wider the tire.

Next Number

This two-digit number, known as the aspect ratio, gives the tire's ratio of height to width. Numbers of 70 or lower indicate a short sidewall fro improved steering response and better overall handling on dry pavement.

R

The "R" stands for radial. Radial ply construction tires has been the industry standard for the past 20 years.

Next Number

This two-digit number is the wheel or rim diameter in inches. If you change your wheel size, you will have to purchase new tires to match the wheel diameter.

Next Number

This two-or three-digit number is the tire's load index. It is a measurement of how much weight each tire can support. You may find this information in your owner's manual. If not, contact a local tire dealer. Note: You may not find this information on all tires because it is not required by law.

M+S

The "M+S" or "M/S" indicates that the tire has some mud and snow capability. Most radial tires have these markings; hence, they have some mud and snow capability.

Speed Rating

The speed rating denotes the speed at which a tire is designed to be driven for extended periods of time. The ratings range from 99 miles per hour (mph) to 186 mph. These ratings are listed below. Note: You may not find this information on all tires because it is not required by law.

Letter Rating	Speed Rating
Q	99 mph
R	106 mph
S	112 mph
T	118 mph
U	124 mph
Н	130 mph
V	149 mph
W	168* mph
Υ	186* mph

• For tires with a maximum speed capability over 149 mph, tire manufacturers sometimes use the letters ZR.

For those with a maximum speed capability over 186 mph, tire manufacturers always use the letters ZR

U.S. DOT Tire Identification Number

This begins with the letters "DOT" and indicates that the tire meets all federal standards. The next two numbers or letters are the plant code where it was manufactured, and the last four numbers represent the week and year the tire was built. For example, the numbers 3197 means the 31st week of 1997. The other numbers are marketing codes used at the manufacturer's discretion. This information is used to contact consumers if a tire defect requires a recall.

Tire Ply Composition and Materials Used

The number of plies indicates the number of layers of rubbercoated fabric in the tire. In general, the greater the number of plies, the more weight a tire can support. Tire manufacturers also must indicate the materials in the tire, which include steel, nylon, polyester, and others.

Maximum Load Rating

This number indicates the maximum load in kilograms and pounds that can be carried by the tire.

Maximum Permissible Inflation Pressure

This number is the greatest amount of air pressure that should ever be put in the tire under normal driving conditions.

UTQGS Information

Treadwear Number

This number indicates the tire's wear rate. The higher the treadwear number is, the longer it should take for the tread to wear down. For example, a tire graded 400 should last twice as long as a tire graded 200.

Traction Letter


This letter indicates a tire's ability to stop on wet pavement. A higher graded tire should allow you to stop your car on wet roads in a shorter distance than a tire with a lower grade. Traction is graded from highest to lowest as "AA", "A", "B", and "C".

Temperature Letter

This letter indicates a tire's resistance to heat. The temperature grade is for a tire that is inflated properly and not overloaded. Excessive speed, underinflation or excessive loading, either separately or in combination, can cause heat build-up and possible tire failure. From highest to lowest, a tire's resistance to heat is graded as "A", "B", or "C".

ADDITIONAL INFORMATION ON LIGHT TRUCK TIRES

Please refer to the following diagram.



Tires for light trucks have other markings besides those found on the sidewalls of passenger tires.

LT

The "LT" indicates the tire is for light trucks or trailers.

ST

An "ST" is an indication the tire is for trailer use only.

Max. Load Dual kg (lbs) at kPa (psi) Cold

This information indicates the maximum load and tire pressure when the tire is used as a dual, that is, when four tires are put on each rear axle (a total of six or more tires on the vehicle).

Max. Load Single kg (lbs) at kPa (psi) Cold

This information indicates the maximum load and tire pressure when the tire is used as a single.

Load Range

This information identifies the tire's load-carrying capabilities and its inflation limits.

TIRE SAFETY TIPS

Preventing Tire Damage

- Slow down if you have to go over a pothole or other object in the road.
- Do not run over curbs or other foreign objects in the roadway, and try not to strike the curb when parking.

Tire Safety Checklist

- Check tire pressure regularly (at least once a month), including the spare.
- Inspect tires for uneven wear patterns on the tread, cracks, foreign objects, or other signs of wear or trauma.
- · Remove bits of glass & foreign objects wedged in the tread.
- · Make sure your tire valves have valve caps.
- · Check tire pressure before going on a long trip.
- Do not overload your vehicle. Check the Tire Information and Loading Placard or User's Manual for the maximum recammended load for the vehicle.

COUPLING TO THE TOW VEHICLE

Follow all of the safety precautions and instructions in this manual to ensure safety of persons, cargo, and satisfactory life of the trailer.

USE AN ADEQUATE TOW VEHICLE AND HITCH

If the vehicle or hitch is not properly selected and matched to the Gross Vehicle Weight Rating (GVWR) of your trailer, you can cause an accident that could lead to death or serious injury. If you already have a tow vehicle, know your vehicle tow rating, and Gross Combination Weight Rating (GCWR) and make certain the trailer's rated capacity is less than or equal to the tow vehicle's rated towing capacity. If you already have (or plan to buy) a trailer, make certain that the tow rating of the tow vehicle is equal to or greater than the GVWR of the trailer, and that the GCWR will be within limits.

^DANGER

Use of a hitch with a load rating less than the load rating of the trailer can result in loss of control and may lead to death or serious injury.

Use of a tow vehicle with a towing capacity less than the load rating of the trailer can result in loss of control, and may lead to death or serious injury. Be sure your hitch and tow vehicle are rated for the Gross Vehicle Weight Rating of your trailer.

TRAILER INFORMATION

Keep a record of the date and approximate mileage when you check the lug nut torque. Note any lug nut that has lost torque. Investigate the reason(s) if the lug nut torque is not maintained after more than one re-torque application, because this indicates there is something wrong with the lug nuts, nut studs, wheels and/or hubs and should be corrected.

Contact your dealer or Reelstrong immediately if you experience any persistent lug nut loosening or any other lug, wheel or axle problems.


In the event of a wheel separation incident, notify the vehicle manufacturer and dealer. Seek prompt professional assistance in assessing the trailer and its gear, and retain, but don't re-use involved lugs, wheels and studs. Don't repair or service the trailer yourself. Call a trained technician.


Lug Nut Torque—Steel Wheels									
Axle Rating Pounds	Stud Size	Dry Torque Foot-Pounds							
3,500 to 7,000	_inch	90-120 (max) ft pounds							
8,000	9/16 inch	170 (max) ft pounds							
9,000	5/8 inch	325 (max) ft pounds							



Reel, Pole and Gas Trailers using ACME-Clamp™, Safelock™, and Securelock™ Technologies


REPLACEMENT PARTS BILL OF MATERIALS ASSEMBLY AND SUBASSEMBLY DRAWINGS








	_				_		_		_	_	_		_		<u> </u>	_		4	7				α	2					<		_	
	VTS	DESCRIPTION	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener	Fastener												SL7K	Drop-In Tension Brake Opt	CUSTOMER	. 6 DWG. NO. SL7K-0000
7	\TERIA	Ğ≻.	4	12	20	4	6	6	8	-	/	ω -	4 c	7 7	4	7	9													Δ	1/12/2019	SHEET 3 OF 6
က	BILL OF MATERIALS	PART NUMBER	Bolt, Hex, 0.63-11x2.25, Grade 8	Bolt, Hex, 0.63-11x1.50, Grade 5	Nut, Top Lock, 0.63-11, Grade C	Washer, Split Lock, 0.63, Zinc-Plated Steel, Grade 8	Screw, Hex, Self-Tapping, 0.25-14x1.00,	Bolt, Hex. 0.50-13x1,25. Grade 5	Washer, Split Lock, 0.50, Zinc-Plated	Bolt, Hex, 0.25-20x0.75, Grade 5	Nut, Top Lock, 0.25-20, Grade C	Washer, General Purpose, 0.63, Zinc- Plated Steel	Bolf, Hex, 0.63-11x2.00, Grade 5	Nut, Top Lock, 0.38-16, Grade C	Washer, 0.38, Zinc-Plated (Oversized	Bolt, Hex, 0.38-16x1.25, Grade 5	Bolt, Hex, 0.25-20x0.88, Grade 5												MATERIAL: TITLE:	FINISH: APPRX WEIGHT:	DATE DATE	DO NOT SCALE DRAWING
	_	ITEM	27	28	29	30	31 Sci	32		34	35		3/	39	40 ×	14	42												Į.		FLEE	IG TRAILERS → nheim, PA 1. 132 info@ree
4		<u>E</u>	2	2	2	<u></u> E	<u>ε</u>	<u></u> m	<u></u> 8	<u>ε</u>	<u>e</u>	m u	w c	<u>) က</u>	4	4	4															PINIESS REEL, POLLING TRAINERS AND SERVICE 283 S. Oak St., Manheim, PA 17545 V: 484-889-8048 F: 888-380-3932 info@reelstrongufle
2												×		рı			5								svis]	ISE SPECIFIED:	DIMENSIONS ARE IN INCH TOLERANCE LIMITS	ANGULAR = ± 1.0* DECIMAL X = ±0.060 DECIMAL XX = +0.010	DECIMAL XXX = ±0.005
9		DESCRIPTION	Chassis Level 2	Tension Brake	Front Jack	Driver's Side Jack	Reel Bar Assembly	Pintle Hitch, 21 Ton	Rubber Mud Flap, 12 x 18	Plate Light	10K Sprung Axle	ST-215/75 R17.5 LR-H Tire, 17.5 x 6.75 6.5 BC Wheel Silver	3/4" Amber LED	Red LED Taillight, 4" Grommet, ar Piatail	3/4" Red LED Light	Breakaway Kit - Battery	Nuera (2) 12-662 DelCity (3ft) 99705	7-Way Socket	Reflective Conspicuity Tape	Reflective Conspicuity Tape	Large Manual Canister	FD-304 MSO	SL7K Manual	Engraved VIN Plate	Class IV (16K) Safety Chain With Clevis - 36" GRADE 70	Trailer Hook-up Label	Warning Decal - Read Manual		UNLESS OTHERW	PROPRIETARY AND CONFIDENTIAL THE INFORMATION CONTAINED IN THIS	DRAWING IS THE SOLE PROPERTY OF ReelStrong, Inc. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOLITHE	WRITEN PERMISSION OF ReelStrong, Inc. IS PROHIBITED.
							-		Ruk			15/75		sed LE		Br	Jera (2		Refle	Refle	۲ ا				.) <u>> </u> ss	_	Warni					
	RIALS	<u> </u>												4			ž															
	MATE	Ø≻	_	_	_		+	-	2	-	_	-2	2	16	7	_		7	9	2	-	_	-	_	- 2							
7	BILL OF MATERIALS	PART NUMBER	Chassis Level 2	TensionBrake-0100	SL7K-0115	SL7K-0115	5014-0100	SL7K-0113	XSB1218LSP	SL7K-0106	SL7K-0054	SL7K-0019	TLM055	TLS010, TLG160, TLP210	TLM005	HE2947 (Part A)	Nuera (2) 12-662 DelCity (3ft) 99705	107544	107949	107949	67670	MSO Rolled	Manual	VIN PLATE	HAC86	UT0033	WarningDecal-2					
∞				Ter																												
		ITEM	_	7	က	4 ч	9	7	∞	6	10	Ξ	12	13	14	15	16	17	8	19	20	21	22	23	24	25	26					
						Ω								O				1				8)					<				


 ∞






















Prospec 2013

February 10, 2016 Version 8.6

Leaf Spring Axle

Prepared For:

REELSTRONG 10KGD 88x64.5

REELSTRONG 10KGD 88x64 5

FAX #:

Phone #:

Customer Part #: SL7K Sprung Axle

E-Mail:

Customer Notes:

Prepared By:

File Name:

Phone #:

FAX #:

E-Mail:

		Cu	stomer Selec	tions		
100	Model and Spindle		Combination	Hubface	Spring Center	Tube
Axle	D100GD Stand	ard, Oil	Single	88.00	64.50	5.00 x HD
	PN	Туре	Width Length	Capacity Descr	iption	Orientation
Springs	072-080-01	Slipper	2.50 30 50	00#/each Rub	ber Bushed	Underslung
	PN	Description				
Hardware	e HAP-158-00, S	ingle Hanger	QTY 1			
	PN	Туре	Size	Description	_	
Brakes	K23-450-00 LH	Electric	12 1/4 x 3	3/8 Forward	Self Adjust	
	K23-451-00 RH					
	PN	Bolt Circle	Capacity	Descri <u>p</u> tio	n	
Hubs	008-430-05	8 on 6.5	10000 #/	pair H-D, 5/8	3 Studs, Grs or C	Dil
	Size	Bolt Circle	Capacity	Wheel Off	set	
Wheels	17.5 x 6.75HC	8 on 6.5	4805 #/e	ach 0.19 In	set	
	Size	Load Range	Capacity	Dual Ca		
Tires	215/75R17.5H	Н	4805 #/e	ach 4540	#/each	
			@ 125 p	si @ 12	5 psi	

Cald	culated Capad	city
Axle Capacity (each axle)	10,000 lbs	(Excluding rims, wheels and tires)
G.A.W.R. (each axle)	9,610 lbs	(Including rims, wheels and tires)
Entire Running Gear	9,610 lbs	(Including rims, wheels and tires)



Prospec 2013


February 10, 2016 Version 8.6

Leaf Spring Axle

Prepared For: REELSTRONG 10KGD 88x64.5

REELSTRONG 10KGD 88x64.5

Customer Part #: File Name:



	Front	Center	Rear	
Hanger Spacing	27.4	N/A	N/A	
Axle Spacing	N/A	N/A	N/A	
	Overall Ht	Radius	Static Loaded Radius	
Tire Dimensions	29.3	15.3	14.0	
Frame Height	19.0			
Min. Fender Height	13.3			
Axle Location	14.0			
Tire Center	5.0			
Static Bump Clearance	e 1.9			
Ground Clearance	7.6			

Unless Otherwise Specified All dimensions Are in Inches and shown at "Rated load" with trailer sitting "level".

If Static Bump Clearance is greater than 2.5", a bump stop should be used to avoid overstressing of leaf springs. Static Bump Clearance of less than 1.5" may limit full suspension movement and result in possible damage to the frame and/or axles when operating on some rough and uneven road surfaces. Tire clearance should always be greater than bump clearance to help prevent tire contact to underbody surfaces in the event of a suspension component failure.



PROSPEC 2013

February 10, 2016 Version 8.6


Leaf Spring Axle

Prepared For: REELSTRONG 10KGD 88x64.5

REELSTRONG 10KGD 88x64.5

Customer Part #:

File Name:




Hubface	Spring Center	Track Width	
88.00	64.50	87.62	
Outside	of tires at the top	96.02	
Inside of	tires at the top	79.22	
Tire to s	ide of hanger	5.80	
Inside of	Brake	74.80	
Brake to	Hanger	3.59	
Hub tip t	o hub tip	96.58	

Unless Otherwise Specified All dimensions Are in Inches and shown at "Rated load"

10K, 12K, 15K, and 13D Hub Groups






ltem	Description	10K, 13D 8 on 6.50	10K, 13D Disc 8 on 6.50	12K Low-Profile 8 on 6.50	12K Hi-Profile 8 on 6.50	12K Disc 8 on 6.50	15K 8 on 275 mm
2	Unitized Oil Seal	010-056-00	010-056-00	010-056-00	010-056-00	010-056-00	010-056-00
3	Inner Bearing Cone	031-022-02 (395S)	031-022-02 (395S)	031-020-02 (3984)	031-020-02 (3984)	031-020-02 (3984)	031-020-02 (3984)
4	Inner Bearing Cup	031-022-01 (394A)	031-022-01 (394A)	031-020-01 (3920)	031-020-01 (3920)	031-020-01 (3920)	031-020-01 (3920)
5	Brake Drum	009-027-01	_	009-028-01	009-028-01	_	009-028-01
5	Brake Drum-ABS	009-027-03	_	009-028-05	009-028-05	_	009-028-05
5A	Brake Rotor	_	070-006-01	_	_	070-006-01	-
5A	Brake Rotor-ABS	_	070-006-02	_	_	070-006-02	-
6	Wheel Mounting Stud	007-115-00 -	007-115-00 -	007-115-00	007-115-00	007-115-00	007-194-00 (std) 007-195-00 (long)
7	Hubs w/Cups & Studs	008-214-05 -	008-214-06 -	008-216-08 -	008-214-08	008-214-10	008-401-05 (std stud) 008-401-06 (long stud)
8	Outer Bearing Cup	031-019-01 (382A)	031-019-01 (382A)	031-021-01 (28622)	031-021-01 (28622)	031-021-01 (28622)	031-021-01 (28622)
9	Outer Bearing Cone	031-019-02 (387A)	031-019-02 (387A)	031-021-02 (28682)	031-021-02 (28682)	031-021-02 (28682)	031-021-02 (28682)
10	Spindle Washer	005-060-00	005-060-00	005-060-00	005-060-00	005-060-00	005-060-00
11	Spindle Nut	006-084-00	006-084-00	006-084-00	006-084-00	006-084-00	006-084-00
12	Tang Washer	005-059-00	005-059-00	005-059-00	005-059-00	005-059-00	005-059-00
13	Oil Cap "O" Ring	010-050-00	010-050-00	010-050-00	010-050-00	010-050-00	010-050-00
14	Oil Cap	021-036-00	021-036-00	021-036-00	021-036-00	021-036-00	021-036-00
15	Oil Cap Plug	046-032-00	046-032-00	046-032-00	046-032-00	046-032-00	046-032-00
16	Wheel Clamp Ring Wheel Nut	033-052-01 006-109-00	033-052-01 006-109-00	033-052-01 006-109-00	033-052-01 006-109-00	033-052-01 006-109-00	
17	Flange Nut (swivel)	_	_	_	_	_	006-118-00
21	Drum Mounting Screw	007-244-00	_	007-244-00	007-244-00	_	007-244-00
22	Rotor Mounting Stud	_	025-014-00	_	_	025-014-00	-
23	Rotor Mounting Nut	_	006-046-00	_	_	006-046-00	_

Electric Brake Parts - Cast Backing Plate After April 2000





Item	Description	Qty Per Brake	121/4" x 33/8" 9K, 10K, 13G GD Part No.	121/4" x 4" 10K, 13D Part No.	121/4" x 5" 12K Part No.	121/4" x 5" 15K Part No.
1	LH Shoe & Lining Kit Contains: LH Primary LH Secondary	1 1 1	K71-499-00 040-351-01 040-350-02	K71-501-00 040-352-01 040-353-02	K71-503-00 040-354-01 040-355-02	K71-503-00 040-354-01 040-355-02
1	RH Shoe & Lining Kit Contains: RH Primary RH Secondary	1 1 1	K71-198-00 040-350-01 040-351-02	K71-500-00 040-353-01 040-352-02	K71-502-00 040-355-01 040-354-02	K71-502-00 040-355-01 040-354-02
2	Backing Plate Assembly	1	036-120-02	036-120-02	036-120-02	036-120-02
5	LH Actuator Arm Assembly RH Actuator Arm Assembly	1 1	047-123-38 047-123-37	047-123-38 047-123-37	047-123-36 047-123-35	047-123-36 047-123-35
6	Wire Clip	3	027-039-00	027-039-00	027-039-00	027-039-00
7	LH Arm/Shoe Retainer RH Arm/Shoe Retainer	1 1	071-455-01 071-455-02	071-455-01 071-455-02	071-455-01 071-455-02	071-455-01 071-455-02
8	Flange Nut	1	006-092-01	006-092-01	006-092-01	006-092-01
9	Magnet Kit Contains: Magnet Retainer Clip Magnet Assembly Magnet Mounting Spring	1 1 1	K71-376-00 027-050-00 042-129-00 046-117-00	K71-376-00 027-050-00 042-129-00 046-117-00	K71-377-00 027-050-00 042-130-00 046-117-00	K71-378-00 027-050-00 042-131-00 046-117-00
10	Centering Spring	2	046-136-00	046-136-00	046-136-00	046-136-00
11	Adjuster Cable	1	071-462-00	071-462-00	071-462-00	071-462-00
12	LH Adjuster Lever RH Adjuster Lever	1 1	071-464-00 071-463-00	071-464-00 071-463-00	071-464-00 071-463-00	071-464-00 071-463-00
14	Adjuster Spring	1	046-137-00	046-137-00	046-137-00	046-137-00
15	LH Adjuster Assembly RH Adjuster Assembly	1 1	048-019-00 048-020-00	048-019-00 048-020-00	048-019-00 048-020-00	048-019-00 048-020-00
16	Dust Shield	1	036-115-21	036-115-22	036-115-23	036-115-23
17	Brake Mounting Screw	7	007-116-00	007-116-00	007-116-00	007-116-00
19	Wire Grommet	1	046-016-00	046-016-00	046-016-00	046-016-00
20	Adjuster Clip (thread end)	1	046-132-00	046-132-00	046-132-00	046-132-00
21	Adjuster Clip (barrel end)	1	046-133-00	046-133-00	046-133-00	046-133-00
26	Brake Mounting Nut	7	006-017-00	006-017-00	006-017-00	006-017-00
27	Brake Mounting Lockwasher	7	005-008-00	005-008-00	005-008-00	005-008-00
28	Return Spring	1	046-119-00	046-119-00	046-119-00	046-119-00